



*Exceptional service in the national interest*

# GEN 3 PARTICLE PILOT PLANT

## *Project Overview and Opportunities*

Jeremy Sment (PI), Presentor

*Concentrating Solar Technologies (8923)*

Contributors: Clifford Ho, Brantley Mills, Matthew Sandlin, Hendrick Laubscher, Luke McLaughlin, Nathan Schroeder, Luis Garcia Maldonado, Shaker Alaqel, Kristina Ji, Madeline Hwang, Madeline Finale, Aaron Overacker, Ansel Blumenthal, Andrea Ambrosini, Evan Bush, Daniel Ray, Kevin Good, Roger Buck, Robert Crandel Francisco Alvarez, Kevin J. Albrecht, Logan Rapp, Mathew Carlson, Margaret Gordon, Jennifer Braid, Josh Stein, Logan Rapp, Abraham Ellis, Robert Lealand



Sandia National Laboratories is a multimission laboratory managed and operated by National Technology and Engineering Solutions of Sandia LLC, a wholly owned subsidiary of Honeywell International Inc. for the U.S. Department of Energy's National Nuclear Security Administration under contract DE-NA0003525.

# AGENDA

October 29, 2024

10:00-10:40 Presentation

10:40-10:55 Q&A

Please log questions during  
presentation in chat.

Gen 3 CSP Program


Particle Pathway

G3P3 Overview

G3P3 Next Steps



Commercialization Pathways

Market Opportunities



GEN 3 CSP  
PROGRAM

# GEN 3 CSP PROGRAM OBJECTIVE




# PROJECT OVERVIEW




## TOPIC 1

- Sandia National Laboratories
- National Renewable Energy Laboratory
- Brayton Energy



## TOPIC 2A

- Brayton Energy
- Hayward Tyler
- Massachusetts Institute of Technology (x2)
- Mohawk Innovative Technology
- Powdermet
- Purdue University



Topic 1 Awardees have the opportunity to incorporate Topic 2A components

## TOPIC 2B

- Electric Power Research Institute
- Georgia Institute of Technology (x2)
- Rensselaer Polytechnic Institute
- University of California, San Diego
- University of Tulsa







# G3P3 ORGANIZATION AND TASK STRUCTURE



(ORGANIZED BY PHASE 3 DOWNSELECTION CRITERIA)



## G3P3 Phases 1 and 2



# GEN 3 CSP PROGRAM OBJECTIVE AND ACCOMPLISHMENTS



# AGENDA

October 29, 2024

10:00-10:40 Presentation

10:40-10:55 Q&A

Please log questions during  
presentation in chat.

Gen 3 CSP Program

## **Particle Pathway**

G3P3 Overview


G3P3 Next Steps

Commercialization Pathways


Market Opportunities




# G3P3 FROM CONCEPT TO ACTUALIZATION




Conceptualization  
Gen 3 CSP, 2017



Component Design and  
Modeling 2018-2019



System Design and  
Commercialization Plan  
2020



SETO Awards Phase 3 to  
Particle Pathway, 2021



Breaking Ground  
February 2023



Top-out  
February 2024



Tower Complete  
Solar Equipment Loaded  
Commissioning underway  
Today

# EXTERNAL AND INTERNAL PARTNERSHIPS



Role	Team Members	
<b>PI / Management</b>	<ul style="list-style-type: none"> <li>• 8923 Concentrating Solar Technologies</li> <li>• 8925 Solar Thermal Testing and Demo</li> <li>• 4823 Project Management</li> </ul>	<ul style="list-style-type: none"> <li>• 4643 Isleta Liaison</li> <li>• 4643 NEPA</li> <li>• 11010 SFO</li> <li>• 6547 Safety Engineering</li> <li>• 4623 Safety Engineering</li> <li>• 8518 ES&amp;H</li> <li>• 10245 Supply Chain</li> </ul>
<b>R&amp;D / Engineering</b>	<ul style="list-style-type: none"> <li>• Sandia National Laboratories</li> <li>• King Saud University</li> <li>• Georgia Institute of Technology</li> <li>• German Aerospace Center</li> <li>• University of Michigan</li> </ul>	<ul style="list-style-type: none"> <li>• CSIRO</li> <li>• U. Adelaide</li> <li>• Australian National University</li> <li>• CNRS-PROMES</li> <li>• University of Texas at Austin</li> </ul>
<b>Integrators / EPC</b>	<ul style="list-style-type: none"> <li>• EPRI</li> <li>• Bridgers &amp; Paxton</li> <li>• Bohannon Huston</li> <li>• Summit Construction</li> </ul>	<ul style="list-style-type: none"> <li>• JT Thorpe</li> <li>• Jon Balis</li> <li>• H+P3/Crane Services</li> <li>• TribalCo rescue and safety</li> </ul>
<b>CSP Developers</b>	<ul style="list-style-type: none"> <li>• SolarDynamics</li> </ul>	<ul style="list-style-type: none"> <li>• Heliogen</li> </ul>
<b>Component Developers / Industry</b>	<ul style="list-style-type: none"> <li>• Carbo Ceramics</li> <li>• Solex Thermal Science</li> <li>• Vacuum Process Engineering</li> <li>• FLSmidth</li> </ul>	<ul style="list-style-type: none"> <li>• Materials Handling Equipment</li> <li>• Allied Mineral Products</li> <li>• Matrix PDM</li> <li>• SSI</li> <li>• Magaldi</li> <li>• Babcock &amp; Wilcox</li> <li>• Albina Co.</li> <li>• Flowserve</li> </ul>
<b>Utility</b>	<ul style="list-style-type: none"> <li>• Saudi Electric Company</li> </ul>	<ul style="list-style-type: none"> <li>• Chugach Electric, Alaska</li> </ul>

# AGENDA

October 29, 2024

10:00-10:40 Presentation

10:40-10:55 Q&A

Please log questions during  
presentation in chat.

Gen 3 CSP Program

Particle Pathway

**G3P3 Overview**

G3P3 Next Steps


Commercialization Pathways

Market Opportunities




# G3P3-USA Construction Timeline

- **March 2021** – Phase 3 awarded
- **May 2022** – Re-issued NEPA complete/Re-baselined schedule
- **September 2022** – Tower construction began
  - **January 2023** – Broke ground
  - **February 2024** – Steel top out
  - **June 2024** – Bridge crane/elevators installed
  - Expected tower completion is **October 2024**
- **June 2024** – CARBO particles delivered
- **July 2024** – CSP equipment lift
  - PHX from VPE has been delayed until late **August 2024**
- **July 2024** – Plan B PHX executed
- **December 2024** – Completion of particle loop assembly
- **January 2025** – Commissioning of the G3P3 System



Near complete G3P3 tower with the existing NSTTF Tower

# System Components



System Overview

Parameter	G3P3-USA
Receiver thermal power	~2 MW <sub>t</sub>
Solar multiple	~2
Particles	CARBO HSP 40/70 ceramic beads
Receiver	Falling particles with SNOUT and StAIR; single slide gate
Heat exchanger	1 MW <sub>t</sub> duty; Moving packed bed; particle flow in shell; 20-25 MPa sCO <sub>2</sub> flow in plates
Particle Lift	Bucket elevator
Power block	~1 MW <sub>t</sub> sCO <sub>2</sub> flow loop
Tower structure	Open





# Tower Construction

- The G3P3 tower is in the final stages of construction



Poured and cured drilled piers and pier caps



Installing "cold" storage bin




Completed first structural steel splice



Tower top out



Completed installation of hot storage bin



Early installation of CSP components (July 2024)






# CAPABILITIES




High-Performance Computing tools for computational particle flow modeling, B. Mills 1514



## Design and Engineering

Cooling fan and motor

Water chiller for pump lubricant (sCO2)




Pump VFD

Pump


Low- and high-temperature recuperators

Dewar and inventory system (needs to be on ground level)


## Unique World Class Test Facilities



Advanced manufacturing and materials, Solex



## Physics-based control systems with engineered safety






# RECEIVER INSTALLATION


- The receiver system has been installed within the tower
  - Receiver installation is ongoing focusing on interconnection with the ducting



Receiver cavity being lifted into the tower



Receiver cavity mounted on a rail system



SNOUT interface with spillage board rails




Gravimetric receiver weigh hopper below the receiver cavity



# RECEIVER GROUND TEST

- Achieved minimum and maximum flow rates (3-12 kg/s)
  - Maximum flow rates (20 kg/s) did not eject particles through the aperture
- Particles flowed through the cavity as expected
- Confirmed SCADA integration with receiver hardware
- Some mass flow rate deviation was observed across the curtain
  - Caused by stock material tolerances
  - Corrections have been made before the installation into the tower
  - PCGV valves may also be integrated as an alternative solution






# STORAGE INSULATION INSTRUMENTATION




- 6 MWh two-tank thermal energy storage
- 122 metric-tons of CARBO HSP 40/70 particles
- Flat bottom tanks with particle riser
- Tanks installed bottom-up with structure construction
- Insulation installation on-going: Planned completion Oct. 2024






# PRIMARY HEAT EXCHANGER

- G3P3-USA is awaiting delivery of two heat exchanger concepts
  - Parallel plate design (Inconel 625) (primary concept)
    - Currently experiencing fabrication delays
  - Shell and tube design (Inconel 625) (backup concept)



Parallel plate PHX core rendering

Shim assemblies prior to furnace loading (diffusion bonding)




Shell and Tube PHX rendering



# SCO<sub>2</sub> LOOP DESIGN UPDATE



- 1 MWt sCO<sub>2</sub> heat rejection loop
- Serves as the heat rejection step in the gen3 CSP cycle – future augmentation to power cycle
- 5 kg/s flow rate, targeted 715 C maximum T<sub>sCO<sub>2</sub></sub>



sCO<sub>2</sub> loop CAD rendering



sCO<sub>2</sub> blower (right) and air cooler HX (left)



sCO<sub>2</sub> blower (heat rejection) (top)  
and sCO<sub>2</sub> pump (bottom)



# DUCTING AND VALVES



- Circular ducting design chosen over square system
  - Minimizes the number of unique parts and fabrication
  - Simplifies design for thermal expansion
  - Simplifying mounting strategy – utilization of off the shelf hardware
- Ducting fabrication is underway



Dual actuation valve below hot storage



Testing of particle flow within the isolation valve



Completed interconnections





In-house construction of the ducting system

# ELECTRIC HEATING




- Utilized for system pre-heating and particle temperature control
- 400 kW packed bed and 200 kW fluidized bed designs
- Designs completed and fabrication/procurement underway

Fluidized heater concept



400 kW heater CAD



Improved packed bed heater performance targets


# SCO2 LOOP GROUND TESTING



- sCO<sub>2</sub> loop “cold” commissioned on ground prior to installation in G3P3 tower
- System pump and sensors characterized
  - Pump curve produced
  - Sensor ranges assessed
- Lessons learned
  - Venturi flow meter unsatisfactory – need for Coriolis flow meter
  - Pressure sensor differential measurement range too low – upgraded instruments needed
- Improved equipment procured
- Equipment installed in G3P3 tower



sCO<sub>2</sub> ground loop assembly during testing





## LESSONS LEARNED



- NEPA (ask for everything you might need, changes can take years)
- Slope of decks for standard construction vs. equipment positions
- Crane design should be led by design team to ensure proper range of motion
- Storage assembly and materials
- Formal review of construction drawings and architect understanding of use (cutouts for ducts)
- SCADA (IT) was a much larger than anticipated
- Ductwork, valves, and pressure system merits dedicated design team
- Management reserve budget was critical

# AGENDA

October 29, 2024

10:00-10:40 Presentation

10:40-10:55 Q&A

Please log questions during  
presentation in chat.

Gen 3 CSP Program

Particle Pathway

G3P3 Overview

**G3P3 Next Steps**

Commercialization Pathways


Market Opportunities

# NEXT STEPS



## What's Next?

- Complete ducting/insulation installation
- Install heat exchanger and complete sCO<sub>2</sub> loop
- Setup SCADA system & calibrate valves/sensors
- Cold flow particles
- Gradually add heat to the system





# MEETING THE CLIMATE CHALLENGE: IMPACT/OPPORTUNITIES




Sand enables:

- Higher power efficiency
- Smaller Lower Cost Receiver
- Abundant sourcing
- Low material cost \$0.58/kW<sub>e</sub>
- LCOS 160 \$/kWh<sub>e</sub>
- 3.7x lower CO<sub>2</sub>-eq than Li+
- Higher temperatures

Brantley Mills, SNL



Electric particle heaters  
Hybrid PV/CSP demo  
RE grid storage



Particle-air heater  
Industrial processes

Electricity generation



# AGENDA

October 29, 2024

10:00-10:40 Presentation

10:40-10:55 Q&A

Please log questions during  
presentation in chat.

Gen 3 CSP Program

Particle Pathway

G3P3 Overview

G3P3 Next Steps


## **Commercialization Pathways**

Market Opportunities


# PROJECTED ELECTRICAL DEMAND FOR SANDIA NM AND KAFB




## Electrical Demand Projections for Sandia NM & KAFB



## U.S. Industrial Electricity Price Projections (EIA\*)



## U.S. Industrial Total Energy Consumption Projections (EIA\*)



\*Energy Information Administration



# SOLAR ENERGY OPTIONS – WHY A HYBRID SYSTEM MAKES SENSE



Model results for a generic system without KAFB constraints



## PV Only

- **LCOE: 5 ¢/kWh**
- No storage

Least cost daytime energy

No energy storage



## PV + BES

- **LCOE: 13 ¢/kWh**
- Storage: 12 hrs

Expensive option to add long duration energy storage

### Modeling Assumptions:

- Calculations for generic system with 12 hours of storage, 100 MW overnight output capacity
- No operational or land area constraints
- 30% investment tax credit, 30-year operational lifetime



## CSP + TES

- **LCOE: 9 ¢/kWh**
- Storage: 12 hrs

Significantly lower cost with long-duration energy storage



## Hybrid


- **LCOE: 8 ¢/kWh**
- Storage: 12 hrs

Combines least cost daytime energy with lowest cost long-duration energy storage

# COMPARING PV AND CSP SYSTEMS COST




When long duration storage needed, CSP+TES is more cost-effective



- Model results for generic solar + storage system with a 100 MW of overnight output capacity
- LCOE = Levelized Cost of Energy

Content: J. Braid




- PV and CSP costs are from historical data
- PV + 10 hrs BES derived from historical PV and BES data




# PHASED BUILDOUT



Contribution to Net Zero and Resilience Goals (J. Braid)




	Phase 0 – PV to Load
	Phase 0– BES to Load
	Phase 1 – PV to Load
	Phase 1 – BES to Load
	Phase 2 – PV to Load
	Phase 2 – BES to Load
	Phase 2 – TES to Load
	Grid to Load
	KAFB/SNL Nominal Load (2033)






# HYBRID SYSTEM COST DRIVERS



- Constraints on the hybrid system imposed by KAFB load, site, and policies increase real costs
- Load shaping includes curtailment and thermal storage efficiency losses for PV

# COST VERSUS LOAD SATISFACTION CURVE, FOR PHASE 2



# COMMERCIAL TRAJECTORY FOR GEN 3 CSP




## Particle-based Tower Projects

- G3P3-USA – Commissioning
- G3P3-KSA – Pre-construction
- Capella - Pre-construction

## Economic Sector Opportunities

- Energy production
- Industrial Process Heat
- Solar Thermochemical Fuels



Particle Receivers

Particle Heat Exchangers

sCO<sub>2</sub> Turbogenerator



# AGENDA

October 29, 2024

10:00-10:40 Presentation

10:40-10:55 Q&A

Please log questions during  
presentation in chat.

Gen 3 CSP Program

Particle Pathway


G3P3 Overview

G3P3 Next Steps

Commercialization Pathways

**Market Opportunities**

# NSTTF THERMAL ENERGY STORAGE TESTBED




MULTIPLE SOURCES OF ENERGY INPUT


THERMAL ENERGY STORAGE DEMONSTRATIONS

INDUSTRIAL SCALE EQUIPMENT DEMONSTRATION

# PARTICLE-BASED SOLAR THERMOCHEMISTRY




Discovery of new STCH materials using machine learning (M. Witman, 8341 Nanomaterials) Nature Computational Science (2023)




Discovery of new High-Entropy Perovskite Oxide Enhances H<sub>2</sub> Production La<sub>1/6</sub>Pr<sub>1/6</sub>Nd<sub>1/6</sub>Gd<sub>1/6</sub>Ba<sub>1/6</sub>Sr<sub>1/6</sub>)MnO<sub>3-δ</sub> (S. Bishop, 1816 Material Physics) ECS Trans. (2023)

$$T_{red} = 1300-1500^{\circ}\text{C}$$



$$T_{ox} = 800-1000^{\circ}\text{C}$$



NSTTF CeO<sub>2</sub> particles heated with solar simulator to split water to produce H<sub>2</sub> (A. McDaniel, 8367 Hydrogen Materials Science) SAND2017-9334R



NSTTF: SrFeO<sub>3</sub> particles heated with solar simulator to isolate N<sub>2</sub> from air and then with Mo<sub>3</sub>Co<sub>3</sub>N particles and H<sub>2</sub> to make NH<sub>3</sub> (A. Ambrosini, E. Bush, 8923 CSP)



# CONCENTRATING SOLAR HEAT FOR HYDROGEN PRODUCTION




CST could help accommodate Green Hydrogen production in a stretched grid infrastructure.

A green hydrogen hub that makes 100 tons/day requires a 200 MW<sub>e</sub> 122 kV transmission line (assume 65% efficiency). High-voltage lines are hard to permit and may have to compete with other users.


A CST hydrogen hub could be islanded away from high power transmission but would only make 15 tons/day of H<sub>2</sub> for a 200 MWt plant (Ma 2022). Land area improves by ~20%.

Scaling particle handling and hermetic receivers are the main barriers to be overcome.



PV array needed to power 100 ton/day H<sub>2</sub> plant

Overlay on Santa Fe map







U.S. DEPARTMENT OF  
**ENERGY**

Office of **ENERGY EFFICIENCY  
& RENEWABLE ENERGY**



**SOLAR ENERGY  
TECHNOLOGIES OFFICE**  
U.S. Department Of Energy

# Acknowledgements

Sandia National Laboratories is a multimission laboratory managed and operated by National Technology and Engineering Solutions of Sandia LLC, a wholly owned subsidiary of Honeywell International Inc. for the U.S. Department of Energy's National Nuclear Security Administration under contract DE-NA0003525

This material is based upon work supported by the U.S. Department of Energy's Office of Energy Efficiency and Renewable Energy (EERE) under the Solar Energy Technologies Office Award Number DE-FOA-0001697-1503.

Disclaimer: The views and opinions of authors expressed herein do not necessarily state or reflect those of the United States Government or any agency thereof

QUESTIONS?

